

APPRAISAL ASSIGNMENT
(Summary) Report Format
Lessee: Heather Barbieri
Property: 1157 Camp Cudge Rd
Coolin, Bonner County, Idaho, 83821

As of
February 15, 2024

Prepared For
Mr. Roger Hall
Real Estate Bureau Chief
Idaho Department of Lands
300 N. 6th Street, Suite 103
Boise, ID 83702

Prepared by
Hall - Widdoss & Company, P.C.
Steven A. Hall, MAI, CCIM
IDAHO CGA-257
Expires 8/11/2024

TABLE OF CONTENTS

SUMMARY OF SALIENT FACTS AND CONCLUSIONS 6

SCOPE OF WORK..... 8

RECORD OWNER..... 11

SALES HISTORY 11

LOCATION OF PROPERTY..... 11

LEGAL DESCRIPTION 11

PURPOSE OF APPRAISAL & DEFINITION OF VALUE..... 11

REASONABLE EXPOSURE TIME..... 11

PROPERTY RIGHTS APPRAISED..... 12

LOCATION MAP 13

PLAT MAP 14

INVENTORY MAP..... 15

SUBJECT PHOTOGRAPHS..... 16

SKETCH.....23

PROPERTY DESCRIPTION 24

HIGHEST AND BEST USE 26

THE APPRAISAL PROCESS..... 28

LAND VALUATION - SALES COMPARISON APPROACH..... 29

LAND SALES TABULATION 35

RECONCILIATION OF LAND VALUATION..... 31

SALES COMPARISON APPROACH - FEE SIMPLE VALUATION.....38

FINAL RECONCILIATION 41

VALUE ESTIMATE AND CERTIFICATION 43

Hall-Widdoss & Company, PC.

Real Property Valuations & Consulting

1001 SW Higgins Avenue, Suite 201

Missoula, MT 59803

Telephone (406) 721-3822; Telefax (406) 721-7848

steve.hall@hall-widdoss.com

caitlinmhelmer@gmail.com

Steven A. Hall, MAI, CCIM
MT & ID General Certified

In Association:

Caitlin M. Helmer

MT General Certified #15449

John Widdoss, ARA

Spearfish, SD (605) 642-8844

May 22, 2024

Mr. Roger Hall
Real Estate Bureau Chief
Idaho Department of Lands
300 N 6th Street Suite 103
PO Box 83720
Boise ID 83720-0050

RE: Appraisal Report, Cottage Site Located at 1157 Camp Cudge Rd, Coolin, Bonner County, Idaho, 83638; Subject to Hypothetical Conditions & Extraordinary Assumptions. IDL Contract 13-110, Contract Modification No. 19; 2024 Priest Lake VAFO, Ground Lease and ULA Appraisals

Dear Mr. Hall:

This letter of transmittal recognizes Contract #13-110, Modification No. 19, dated 9/06/2023 between the State of Idaho, Department of Lands and the firm of Hall – Widdoss & Company, PC. Please be advised this report is being prepared with reference to the 2024 sales catalog, as has been done in the past. As a result, this appraisal report is submitted, in compliance with the terms of the Appraisal Instructions/Scope of Work, 2024 Priest Lake VAFO Appraisals and that this VAFO appraisal report presents a value for the cottage site as a “vacant & unimproved” and also a Fee Simple market value for the property that includes all site improvements & structural improvements identified as IDL Approved Improvements (approved Personal Property). Please be advised this report, in conjunction with the Sales Catalog previously submitted & approved, constitutes compliance with the terms of the Appraisal Instructions/Scope of Work, Priest Lake Cottage Sites, specifically with regard to Modification #19.

This report is submitted as being in full compliance with the 2024-2025 Uniform Standards of Professional Appraisal Practice (USPAP) as promulgated by the Appraisal Standards Board of the Appraisal Foundation. In addition, the appraisal presented is intended to be in full compliance with all applicable laws & regulations affecting this service & report in which jurisdiction the subject property is located.

This is a single-family residential/recreational cabin site located on a lake front lot to Priest Lake. The cottage site, as vacant & unimproved is described in the body of this report. This cottage site has a specific size, front foot of lake shore, specific road access, topography, ground cover, and utility access that are all weighted as to a scale of measuring the quality of the lot. Private road access is maintained by Homeowner Association(s); commonly stated as an HOA. The site is serviced by electricity & telephone but there is no natural gas to the area and for the vacant condition of the lot, there is no sewer and/or water as part of the lot value.

*Appraisals and Consultations in Acquisitions/Dispositions, Feasibility Studies,
Partial Interests, Condemnation & Litigation, Investment Analysis.*

From review, the subject lot is not regulated by an existing zoning district. The subdivision plat filed in Bonner County contains Conditions, Covenants & Restrictions, more commonly known as CC&Rs. This regulates the individual cottage site for a single-family residential use, no further subdivision of the lot, as set forth in that plat CC & Rs. No more than one single-family dwelling unit and such associated accessory structures are allowed.

The Personal Property is defined as a residential/recreational single residential unit (together with any/all ancillary structures). The specific details of these improvements are found in the Summary of Salient Facts section AND the Property Description section. The latter includes the photographs I have taken of the property which clearly reflect the land's qualities as well as the described improvements (design, size, quality, age/condition, and features as well as a discussion of the layout/floor plan. The final point of discussion includes the site improvements such as decks/patios, dock area, boathouse, garages, storage buildings, guest quarters, etc.

Please reference the scope of work section of this report for important information regarding the scope of research and analysis for this appraisal, including property identification & inspection, and an analysis of highest and best use analysis and valuation methodology. Your attention is directed to the Limiting Conditions and Assumptions section of this report. Acceptance of this report constitutes an agreement with these conditions and assumptions. In particular, I note the following:

Hypothetical Conditions: Hypothetical condition that the underlying site represents a 'VACANT AND UNIMPROVED' condition and value of the cottage site as based on that definition. The purpose of the appraisal is to provide an indication of market value for the underlying cottage site to establish a ground lease for this parcel. No personal property is being valued in this appraisal. As the personal property does exist, to value this property as 'Vacant & Unimproved' requires this hypothetical condition.

Extraordinary Assumptions pertaining to this value opinion consists of the agreement between client and appraiser that it is assumed the condition of the cottage site observed on the date of inspection is the same condition of this property as of the date of value of February 15, 2024.

I certify that I have no present or contemplated future interest in the property beyond the value opinions expressed herein. The appraiser has performed prior services regarding the subject within the previous three years of the appraisal date, as noted.

Based upon my investigations, studies and analyses, it is my opinion the encumbered *fee simple* market value of the subject property, reflecting the Extraordinary Assumption relative to IDL Approved Improvements & excluding any boat lifts or PWC lifts and excluding the dock, as of February 15, 2024, is:

One Million Two Hundred Sixty-Seven Thousand Dollars

\$1,267,000

Further, it is my opinion the market value of the subject property defined herein as the "vacant & unimproved" cottage site (*Land Only*), reflecting the hypothetical condition of that definition of "Vacant & Unimproved" and the Extraordinary Assumption regarding date of inspection vs. the effective date of value denoted herein as February 15, 2024, is:

One Million Two Hundred Sixty-Seven Thousand Dollars

\$1,247,000

Finally, it is my opinion the market value of the subject property defined herein as the Leasehold Personal Property (IDL Approved Improvements Only), reflecting the hypothetical condition of the cottage site as “Vacant & Unimproved” and the Extraordinary Assumption relative to IDL Approved Improvements, excluding any boat lifts or PWC lifts, dock improvements & all appliances, as of February 15, 2024, is:

Twenty Thousand Dollars

\$20,000

Your attention is invited to the data found within the body of this report which, in part, is the foundation of this conclusion. I wish to thank you for this opportunity to be of service. If there are any questions or issues that need attention, please do not hesitate to contact me.

Respectfully submitted,
Hall - Widdoss & Company, P.C.



Steven A. Hall, MAI, CCIM
ID Certified General CGA-257
Expires August 11, 2024

SUMMARY OF SALIENT FACTS AND CONCLUSIONS

PROPERTY IDENTIFICATION

Land: The chart below reflects the site characteristics as the vacant & unimproved cottage site.

Site Description		1157 Camp Cudge Rd	Lot 6, Block 1, State Subdivision - Camp Cudge Landing
Size		36,590 Sq. Ft.	Lease No. R100385
Size (Acres)		0.84 Acres	
Waterfront - Straight Across		121.90 Front Ft.	122 For valuation purposes, frontage is rounded to whole #.
Waterfront - Plat Dimension		145' +/- Front Ft.	
Average Depth of Lot		284' +/- LF	
Road Frontage/Access		Site has South Camp Cudge Road extending NE/SW along the eastern boundary of the site. The direct access to the subject site is from this road, through and across Lot 7, to the subject. This is a shared driveway with Lot 7 which allows each tract access to their respective lots. The parcel has deeded lake frontage to Priest Lake.	
Road-to-Building Site	3-4	From road to the end of shared driveway, this is more of a moderate to steeper slope. The building site is located toward the water & there is a gentle to moderate slope from the parking area down to the building site. There is a steeper slope east of the building site.	
Shore-to-Building Site	4-5	From shoreline-to-building site, this is a gentle to moderately sloping area where the existing cabin site is built into the hillside giving this a modified rating consistent with the 2018 appraisal. The cabin site is situated an estimated 10' +/- above the shoreline so access between shore & cabin is rated at a minimum of 4-points.	
Shoreline	4	Tract has a predominately sandy beach with a slight slope to a forested area which represents a gentle to moderate slope to the elevated building site. The shoreline/beach area meanders slightly but key is the expansive sandy beach. This is considered a premium shoreline/beach characteristic.	
Lake Depth	2	Shallow lake depth with previous ratings at 2 points. The shallow area is not sufficient to classify this as having dock development challenges so rating is 2 points. This is an expansive sandy shoreline/beach area with sandy/gravel lake bottom.	
Topography-General Narrative	13+	Topography consists of a gently sloping terrain from shoreline/beach to the toe of the forested hillside & then a gentle-moderate slope to the elevated building site. The 2018 & the 2023 rating was shown at 4-5 points to recognize the building site that is elevated above the shoreline some 10' +/- . From the road-to-building site (assume this is eastern boundary of site), the topography is a moderate to steeper slope down to the building area. In view of the sales of Lots 4 and 5, South Shores Circle and support from other VAFO sales where similar topography have been classified like this property, this rating best supports a rating of 3-4 points. Consistent with the 2018 & 2023 valuation of this property, I have concluded with a rating of 7-8 points for overall topography representing road-to-building and shore-to-building.	
Shape		Plat shows this to be mostly rectangular in shape although the western boundary (shoreline) is irregular; please see maps for better visualization.	
Vegetative Cover		Tract has moderate timber cover with deciduous understory; mix of conifers and deciduous trees/bushes. As photos demonstrate, there is significant downfall (timber laying on the surface of the lot).	
Utilities		Electrical power & phone to site boundary per SOW. Valuation of lot does not incl. well, septic system, building pad, dock, and shoreline improvement per vacant & unimproved.	
Street Improvements		Access is via East Shore Road, a two-lane paved road, to Canoe Point Road & then to N. Camp Cudge Road. There is a juncture where South Camp Cudge Road veers south to Lots 6 & 7. These latter two roads are assumed to be located on Endowment land. Primary legal access is Camp Cudge Road from Canoe Point Road & these are gravel & dirt roads assumed to be maintained by the local association. The subject and Lot 7 have a shared driveway off South Camp Cudge Road and I assume there is an agreement in-place for the repair & maintenance of that shared driveway and for South Camp Cudge Road given these are the only 2 lots serviced by this one lane road.	
Zoning/Land Use		According to Bonner County, the property is not zoned. The subject site is regulated by the Conditions, Covenants & Restrictions (CCRs) recorded as part of the subdivision plat. Specifically, the subject is restricted to single family residential use only. It allows for one dwelling and ancillary improvements including guest house, garage and outbuildings such as storage sheds, boathouse, outhouse, etc.	
Flood Hazard		Property is a lake front tract. The shoreline area is subject to seasonal fluctuations in water depth. The building site is not in a flood hazard zone based on information available.	
Easements/Encroachments		Site has a shared driveway off Camp Cudge Rd South that dead-ends at the north boundary of Lot 7 (south boundary Lot 6). The driveway extends from that point traveling west & then N/NW to the subject south boundary. There is an assumed easement for this shared driveway, which incorporates a use & repair/maintenance agreement with between these two lots. There is no existing phone or electrical service to this lot. In 2013, the lessee stated the closest access to electricity was 565 feet south of Lot 7 & to gain access to electrical service would require an easement over Endowment lands, through Lot 7. For the valuation of Lot 7, electrical service was discovered to exist. Currently, there is no electricity to Lot 6, so it is recognized the use of a generator is required (or combination of generator & solar panels). Lessee had previously indicated there is no septic system on this lot. They have used an outhouse but the SOW requires I assume a drainfield location exists.	

The 2018, 2021, 2022 & the 2023 valuations of this cottage site had shown an aggregate rating of 13 points although it could be argued the lot has the potential for 14 points when considering the road-to-building site that, through Lot 7, is more moderately sloping (higher rating). The slope from shoreline-to-building site is easily considered 4-5 points. Looking at the premiere feature of the expansive sandy beach area & shoreline usability, this is a higher rated site. The shallow depth (a more minor consideration) and the slopes from east down to west provide emphasis to the 13+ rating. None of this discussion addresses the fact the lot has no subdivision to the north & that there are only 2 lots in this southern part of Camp Cudge Landing. That is viewed both positively (buffer & seclusion) & negatively since the access road has cost share from only these two lots (Lots 6 & 7).

Improvements: The Personal Property is included in this appraisal. The table below is a summary of the pertinent characteristics of the improvements (site improvements and structural improvements) that are defined herein as Personal Property, the definition of that term is identified in the sales catalog.

General Description					Foundation/Heating, Ventilating, A/C And Other Items				
Units	One	X	Ancillary Residential Units		N	Issues/Components		Remarks	
# of Stories	One story	X	1.5 Story	2 Story		Settlement	N		
Type	Det	X	Attached			Sump Pump	N		
Quality	Low Cost					Evidence of Infestation	N		
Design	Bungalow					Dampness	N		
Year Built	1925		County shows this was built in 1925 and the cabin contains 592 SF plus the EFP (enclosed front porch) of 77 SF.			EBB	N		
Condition	Old/Rustic					Elec. Wall Htrs	N		
Effective Age	50+					Forced Air Furnace	N		
Bathrooms	0					Cooling System	N		
Finished Area Above Grade	592					Wall Units	N		
Basement/Lower Level	0					Window Units	N		
Basement Finish	0					Central	N		
Attic	0					Fireplace/Wood Stove	1	Rock FP in living room.	
Utilities	None					Specialty Site Impvts.	X	Firepit, paths, parking area	
						Appliances		None	
Exterior Description					Interior Description				
Foundation	Post and pier foundation					Floors	Softwood flooring		
Exterior Walls	Mix of horizontal & vertical siding-painted.					Walls	T&G wood plank walls		
Roof Surface	Metal					Trim/Finish	Rustic wood		
Specialty Siding Elements	None					Ceiling Finish	no ceiling finish (exposed rafters)		
Gutters & Downspouts	None					Bath Floor	N/A		
Window Type	Single pane windows with storms/screens					Bath Wainscot	N/A		
Storm sash included	Yes		No	X		Deck/Porch/Patio(s)		107	SF
Screens	Yes	X	No			Garage (SF)		0	SF
Amenities	Lakeside deck on west side functions as entry porch (5' X 8'). This porch is deteriorated & appears unsafe.					Other Living Area		0	SF
Fireplace/Wood Stove	Fireplace	Y	Wd Stove	N	FP insert	N	Dock (SF)		0
Fencing	None	X				Boathouse (SF)		0	SF
Other Items	None	X				Seawall/Retaining Wall		0	LF
In addition to the main cabin, there is a building that was previously a guest cabin/storage building. The roof has collapsed & this is a detrimental condition to marketability. This is debris that has to be removed.						Main cabin appears to be a dry cabin as the former lessee stated there is no water system and no septic system. There is evidence of 2 plastic tanks above cabin & an above ground pump system to get water from lake to these tanks & then gravity flow to the cabin. None of that water system is truly functional without a sewage disposal system. No electricity, no plumbing, no water, etc. At best, this is a dry cabin.			
Appliances	Ref	0	Range/Oven	0	DW	0	Lessee has excluded everything so no antique wood stove, no refrigerator, no R/O; no appliances at all.		
	Microwave	0	W/D	0	Gar. Disp.	0			
Room Count - Above Grade	Rooms	3	Bedrooms	1	Bathrooms	0.0			
Other Living Area	Old, fully deteriorated structure								

VALUE INDICATIONS

Land Value:	\$1,247,000
Cost Approach:	N/A
Sales Comparison Approach	\$1,267,000
FINAL OPINION OF VALUE – REAL PROPERTY	<u>\$1,267,000</u>
FINAL OPINION OF VALUE – PERSONAL PROPERTY	<u>\$20,000</u>

Effective Date February 15, 2024

SCOPE OF WORK

This was defined in the sales catalog/project report and will not be repeated here except for the very specific conditions imposed by the Scope of Work.

1. **Client:** The client is the Idaho Department of Lands (IDL).
2. **Intended user:** The intended user is the Idaho Department of Lands (IDL). Although it is recognized the individual cottage site Lessee will be provided a copy of this Appraisal, the Lessee is not an intended user of the appraisal. For the VAFO appraisals, the potential bidders are not recognized as intended users.
3. **Purpose/Intended use:** The Purpose of this appraisal is to provide an opinion of the market value of the cottage site, as though “Vacant & Unimproved.” The intended use recognizes the Idaho Constitution, Article IX, Section 8 that provides, “no state lands shall be sold for less than the appraised price.” To establish a ground lease rate, it is necessary that the market value of the vacant cottage site be established through an appraisal. Further, the ground lease rate is set by the State of Idaho which is then applied to the market value of the lot in establishing the ground rent.
4. **Type of value:** The type of value, as required by Scope of Work, is market value. That term has been defined within this report.
5. **Effective Date of Value:** The effective date of appraisal is February 15, 2024, which is not consistent with the date of inspection. This is a current value assignment based on the extraordinary assumption as to date of inspection/observation and the effective date of value. The report date is that date shown on the letter of transmittal which coincides with the final report delivery to the client.
6. **Subject characteristics:** Deals with the extent of the subject property such as inspection/property viewing, property rights appraised, etc. This requires further address which is reflected within this appraisal.
7. **Assignment conditions:** Refers to hypothetical conditions and special or extraordinary assumptions & limiting conditions. Please refer to the paragraphs below regarding these issues. The site valuation reflects a hypothetical condition that the cottage site is viewed as though vacant and unimproved, ignoring for valuation purposes, any lessee personal property.
8. **Prior Services:** I have been involved in an appraisal of the subject cottage site as of January 15, 2013, and again in 2019, then as a VAFO appraisal in 2022 and a Ground Lease appraisal in 2023.

(6. continuation) As identified in the Appraisal Instructions/Scope of Work, Priest Lake Cottage Sites, Item II. states “*At a minimum, the appraisal is to comply with the reporting requirements under Standards Rule 2-2(b) of the USPAP for a Summary Appraisal. The Appraisal Report, as described in USPAP, shall be used to support each individual lot appraisal. A report shall include photos, addenda, plats, maps, etc. that support the facts and the opinion of market value presented in the appraisal. All appraisal report forms must be in compliance with the current version of USPAP.* Under USPAP 2024-2025 an Appraisal Report or a Restricted Report are the classifications of the written report. In historic context, this is further classified as a narrative appraisal report (a summary appraisal report).

For this appraisal, the extent of the subject inspection involved a viewing of the exterior boundaries of the site (at least, to the extent possible because of snow cover). The personal property is included in this appraisal and the assignment includes my personal observations of

the personal property including the measurement of the improvement(s) and an interior inspection of the property improvement(s), if possible. The site view and site analysis reflect the State Subdivision plat as recorded in Bonner County and it incorporates the Overlay maps of the recorded State Subdivisions with the Inventory Surveys provided by JUB Engineers, Inc. The Personal Property described herein is my personal observations and the exterior measurements of these improvements. I have also viewed county records for verification. ***“Clarification to the Scope of Work: If the improvements have changed since the provided 2011 inventory survey, plats, and maps, it is assumed they are IDL approved unless otherwise stated.” Again, for purposes of this appraisal, no Personal Property is being appraised.***

The appraisal assignment reflects **State Endowment Trust Land Information** specifically Idaho Department of Lands mission is to manage State Endowment Trust Lands (State Trust Lands) in a manner that will maximize long-term financial returns to the Beneficiary Institutions. The IDL mission is a constitutional mandate and is overseen by the State Board of Land Commissioners. State Trust Lands are not managed for the public at large and should not be referred to as public lands or open space, either specifically or in a generic sense.

These are working lands producing revenue for the Beneficiary Institutions. IDL has had a leasing program for recreation residential sites since the 1920’s. What began as a simple opportunity to lease State Trust Land for use as primitive cabin sites has evolved into the existing cottage site developments with a range of structure types from large expensive structures to quaint cabins. The subject neighborhood plat has been recorded. The rights and obligations associated with the platting, recording CCRs, and forming of neighborhood associations will be assumed to be in-place and operating at time the lot has been appraised.

For the reader’s edification, I have incorporated definitions for hypothetical conditions and extraordinary assumptions. These definitions are taken from the USPAP 2024-2025.

“HYPOTHETICAL CONDITION: a condition, directly related to a specific assignment, which is contrary to what is known by the appraiser to exist on the effective date of the assignment results, but is used for the purpose of analysis. ***Comment:*** Hypothetical conditions are contrary to known facts about physical, legal, or economic characteristics of the subject property; or about conditions external to the property, such as market conditions or trends; or about the integrity of data used in an analysis.”

“EXTRAORDINARY ASSUMPTION: an assignment-specific assumption as of the effective date regarding uncertain information used in an analysis which, if found to be false, could alter the appraiser’s opinions or conclusions. ***Comment:*** Uncertain information might include physical, legal, or economic characteristics of the subject property; or conditions external to the property, such as market conditions or trends; or the integrity of data used in an analysis.”

The use of extraordinary assumptions and hypothetical conditions within the report should be viewed within context that their use might have affected the assignment results.

USPAP states there to be additional reporting requirements when the appraisal involves a hypothetical condition and, it is assumed equally, when there is an extraordinary assumption. This is necessary to ensure the intended user(s) understands:

- (a) *the improved subject property does not yet, in fact, exist as of the date of the appraisal;*
- (b) *the analyses performed to develop the opinion of value are based on a hypothesis, specifically that the improved subject property is assumed to exist when in fact it does not exist;*
- (c) *certain events need to occur, as disclosed in the report, before the property appraised with the proposed improvements will in fact exist; and*
- (d) *the appraisal does not address unforeseeable events that could alter the proposed property improvements and/or the market conditions reflected in the analyses.*

The client requested an opinion of the market value for the Cottage Site as Vacant & Unimproved for the basis in forming a ground lease amount. It is a condition of this appraisal that the underlying site represents a “VACANT AND UNIMPROVED” condition so the existing personal property is assumed to “not exist.” That is the reason for the hypothetical condition to this valuation analysis.

Relevant to the preceding paragraph, factual market data gathered or researched for this appraisal includes vacant residential/recreational land sales. For purposes of helping the client in conflict situations, the assignment also included sales research of improved sales.

It is recognized that Idaho is a non-disclosure State and verification of sales is commonly handled through real estate agent confirmation as well as buyer and/or seller verification. There are times when the confirming party does not wish to be identified or where the price is not to be divulged. All of these elements are considered appropriate and common under peer review. I have relied upon the Selkirk Realtors MLS service and the Coeur d’Alene Realtors MLS service to assist in the appraisal research for Priest Lake.

It is recognized that I lack special expertise or knowledge with respect to the detection and measurement of hazardous substances. For this appraisal, I have not been provided either a Phase I or Phase II environmental audit relating to this topic for any of the lessee personal property improvements. I have assumed there to be no environmental concerns relating to this cottage site, which is a typical assumption & limiting condition.

RECORD OWNER

According to the information provided by IDL, the current Lessee for this property is shown as follows:

Lessee :Heather Barbieri
Lease # :Lot 6, Block 1, State Subdivision - Camp Cudge Landing

SALES HISTORY

There have been no recent or relevant transfers of ownership for the subject property within the previous three years. This is endowment land administered by the Idaho Department of Lands.

LOCATION OF PROPERTY

The property being appraised is located in Bonner County, Idaho. More specifically, the property is located in the Coolin area (east side of Priest Lake). The street address for the property is identified as 1157 Camp Cudge Rd, Coolin, Idaho.

LEGAL DESCRIPTION

According to the IDL provided information and based on county records, the subject property is more particularly identified as follows:

Lot 6, Block 1, State Subdivision - Camp Cudge Landing

PURPOSE OF APPRAISAL & DEFINITION OF VALUE

The purpose of the appraisal is to provide an opinion of the ***Fee Simple market value*** of the individual cottage site, described as the subject property. The valuation reflects the fee simple value of the cottage site, as "Vacant & Unimproved." The definition of market value was contained in the sales catalog.

REASONABLE EXPOSURE TIME

This was discussed and analyzed within the sales catalog. In summary, the market value of the subject property reflects a reasonable exposure time summarized as follows: For calendar year 2023, the sales of improved residential property along Priest Lake (East and West) resulted in the following for exposure time (Days on Market or DOM) as derived from the Coeur d'Alene MLS and the Selkirk MLS. The exposure times ranged from 0 DOM to 193 DOM with an average of 60 DOM and a median of 53 DOM.

For calendar year 2022, the sales of improved residential property along Priest Lake (East and West) resulted in the following for exposure time (Days on Market or DOM) as derived from

the Coeur d'Alene MLS and the Selkirk MLS. The exposure times ranged from 4 DOM to 158 DOM with an average of 65 DOM. The limited inventory and the strong demand that has been demonstrated through the pandemic of 2020-2021 clearly indicates exposure time to be reduced from more historic levels.

For the calendar year 2021, the sales of improved residential property in the Priest Lake area (East & West), resulted in the following for exposure time (Days on Market or DOM) as derived from the Coeur d'Alene MLS and the Selkirk MLS. The exposure times ranged from 4 DOM to 158 DOM with an average of 65 DOM.

For land sales, the statistics on Days-On-Market (DOM) have shown 2023 reflecting 35 DOM with 2022 showing 127 DOM and 2021 showing 166 DOM. The average or mean of these three-years was 115 DOM.

PROPERTY RIGHTS APPRAISED


The subject property is being valued on the basis of 1.) a site condition of “vacant & unimproved” and 2.) the valuation of the encumbered fee simple estate which includes the land (as vacant & unimproved) together with all of the site & structural improvements (IDL approved improvements).

The appraisal reflects the fee simple title to the property pursuant to Scope of Work. It is necessary to understand that fee simple title can have encumbrances that affect some of those rights associated with fee simple estate. In this appraisal, there are commonly accepted easements for utility services such as electrical power, telephone and cable and, in some cases, there are easements for buried services such as community or private sewer. There are also shared driveway easements which I have not found to be economically burdensome to the underlying site value. If there is an easement(s) that impacts use & value, I will provide that discussion & analysis.


The appraiser was previously provided a map exhibit with the Notice to Proceed (originally provided in Summer of 2013) showing all approved improvements. If any existing improvements are NOT approved by the IDL and/or are not legally constructed, as required by the building authority having jurisdiction, the appraiser is to note these improvement(s) in the appraisal but is NOT to include these in the valuation of the approved improvements.

“Clarification to the Scope of Work: If the improvements have changed since the provided 2011 inventory survey, plats, and maps, it is assumed they are IDL approved unless otherwise stated.”

LOCATION MAP



PLAT MAP



STATE SUBDIVISION-CAMP CUDGE LANDING

A PORTION OF SECTION 22,
TOWNSHIP 62 NORTH, RANGE 4 WEST,
BOISE MERIDIAN,
BONNER COUNTY, IDAHO


J-U-B ENGINEERS, INC.
14-B ENGINEERS, INC.

J-U-B ENGINEERS, Inc.
7525 Meadows Way
Coeur d'Alene, Idaho 83815
Phone: 208.762.8287

DWG. NAME: 20-11-039, Camp Cudge Landing
DR. DPG CH. QUM/DRB SHEET 3 OF 3
SCALE: 1"=400' DATE: December 2012 PROJ. NO.: 20-11-035

INVENTORY MAP

THIS DOCUMENT IS INTENDED AS A TOOL FOR USE BY IDAHO DEPARTMENT OF LANDS TO AID IN THE MANAGEMENT OF ENDOWMENT LAND WITHIN THIS SUBDIVISION



SUBJECT PHOTOGRAPHS



ABOVE: View south along Camp Cudge Rd S. from NE corner of lot. (0100)



ABOVE: Same NE corner area but looking west along north boundary. (0099)



ABOVE: View west from approximate center of lot (N/S) looking westerly. (010)



ABOVE: View NW from south boundary of lot at end of shared driveway. (0105)

SUBJECT PHOTOGRAPHS



ABOVE: View west from the shared driveway on the south boundary. (0106)



ABOVE: Same south boundary location but looking NE into the area of site, east of building site. (0107)



ABOVE: View NW showing the south (left) and east elevations of primary cabin. (0108)



ABOVE: View to the NE from the east side of the primary cabin showing steeper hillside area & water tanks. (0109)

SUBJECT PHOTOGRAPHS



ABOVE: View east along the north boundary from the NW corner of lot. (0119)



ABOVE: View south from the NW corner of lot. (0120)



ABOVE: View from the shoreline/beach to cabin. (0121)



ABOVE: View NE from the SW corner of lot showing the cabin location & gentle slope to building site. (0124)

SUBJECT PHOTOGRAPHS



ABOVE: View north from the SW corner of lot. (0125)



ABOVE: Same location but looking east along the south boundary. (0123)



ABOVE: View west showing the east side elevation of cabin. (0112)



ABOVE: View of the west elevation of cabin. (0122)

SUBJECT PHOTOGRAPHS



ABOVE: View from cabin looking at shoreline/beach. (0145)



ABOVE: View of west side of living room from the SW entry looking toward the kitchen. (0127)



ABOVE: View of kitchen/dining. (0132)



ABOVE: Screened-in porch from kitchen. (0134)

SUBJECT PHOTOGRAPHS



ABOVE: View from kitchen to the west side of living room & the SW entry. (0129)



ABOVE: Living room with FP on the south wall. (0130)



ABOVE: Another view of the living room. (0131)



ABOVE: View of the bedroom. (0140)

SUBJECT PHOTOGRAPHS



ABOVE: Close-up of the damaged storage building. (0111)




ABOVE: Close-up view of the excluded dock improvement. (0117)

BUILDING SKETCH

SKETCH ADDENDUM

File No. _____

Borrower _____				
Property Address _____				
City _____	County _____	State _____	Zip Code _____	
Lender/Client _____		Address _____		



PROPERTY DESCRIPTION

Land: The chart below reflects the site characteristics as the vacant & unimproved cottage site.

Site Description		1157 Camp Cudge Rd	Lot 6, Block 1, State Subdivision - Camp Cudge Landing
Size		36,590	Lease No. R100385
Size (Acres)		0.84	
Waterfront - Straight Across		121.90	122 For valuation purposes, frontage is rounded to whole #.
Waterfront - Plat Dimension		145' +/-	
Average Depth of Lot		284' +/- LF	
Road Frontage/Access		Site has South Camp Cudge Road extending NE/SW along the eastern boundary of the site. The direct access to the subject site is from this road, through and across Lot 7, to the subject. This is a shared driveway with Lot 7 which allows each tract access to their respective lots. The parcel has deeded lake frontage to Priest Lake.	
Road-to-Building Site	3-4	From road to the end of shared driveway, this is more of a moderate to steeper slope. The building site is located toward the water & there is a gentle to moderate slope from the parking area down to the building site. There is a steeper slope east of the building site.	
Shore-to-Building Site	4-5	From shoreline-to-building site, this is a gentle to moderately sloping area where the existing cabin site is built into the hillside giving this a modified rating consistent with the 2018 appraisal. The cabin site is situated an estimated 10' +/- above the shoreline so access between shore & cabin is rated at a minimum of 4-points.	
Shoreline	4	Tract has a predominately sandy beach with a slight slope to a forested area which represents a gentle to moderate slope to the elevated building site. The shoreline/beach area meanders slightly but key is the expansive sandy beach. This is considered a premium shoreline/beach characteristic.	
Lake Depth	2	Shallow lake depth with previous ratings at 2 points. The shallow area is not sufficient to classify this as having dock development challenges so rating is 2 points. This is an expansive sandy shoreline/beach area with sandy/gravel lake bottom.	
Topography-General Narrative	13+	Topography consists of a gently sloping terrain from shoreline/beach to the toe of the forested hillside & then a gentle-moderate slope to the elevated building site. The 2018 & the 2023 rating was shown at 4-5 points to recognize the building site that is elevated above the shoreline some 10' +/- . From the road-to-building site (assume this is eastern boundary of site), the topography is a moderate to steeper slope down to the building area. In view of the sales of Lots 4 and 5, South Shores Circle and support from other VAFO sales where similar topography have been classified like this property, this rating best supports a rating of 3-4 points. Consistent with the 2018 & 2023 valuation of this property, I have concluded with a rating of 7-8 points for overall topography representing road-to-building and shore-to-building.	
Shape		Plat shows this to be mostly rectangular in shape although the western boundary (shoreline) is irregular; please see maps for better visualization.	
Vegetative Cover		Tract has moderate timber cover with deciduous understory; mix of conifers and deciduous trees/bushes. As photos demonstrate, there is significant downfall (timber laying on the surface of the lot).	
Utilities		Electrical power & phone to site boundary per SOW. Valuation of lot does not incl. well, septic system, building pad, dock, and shoreline improvement per vacant & unimproved.	
Street Improvements		Access is via East Shore Road, a two-lane paved road, to Canoe Point Road & then to N. Camp Cudge Road. There is a juncture where South Camp Cudge Road veers south to Lots 6 & 7. These latter two roads are assumed to be located on Endowment land. Primary legal access is Camp Cudge Road from Canoe Point Road & these are gravel & dirt roads assumed to be maintained by the local association. The subject and Lot 7 have a shared driveway off South Camp Cudge Road and I assume there is an agreement in-place for the repair & maintenance of that shared driveway and for South Camp Cudge Road given these are the only 2 lots serviced by this one lane road.	
Zoning/Land Use		According to Bonner County, the property is not zoned. The subject site is regulated by the Conditions, Covenants & Restrictions (CCRs) recorded as part of the subdivision plat. Specifically, the subject is restricted to single family residential use only. It allows for one dwelling and ancillary improvements including guest house, garage and outbuildings such as storage sheds, boathouse, outhouse, etc.	
Flood Hazard		Property is a lake front tract. The shoreline area is subject to seasonal fluctuations in water depth. The building site is not in a flood hazard zone based on information available.	
Easements/Encroachments		Site has a shared driveway off Camp Cudge Rd South that dead-ends at the north boundary of Lot 7 (south boundary Lot 6). The driveway extends from that point traveling west & then N/NW to the subject south boundary. There is an assumed easement for this shared driveway, which incorporates a use & repair/maintenance agreement with between these two lots. There is no existing phone or electrical service to this lot. In 2013, the lessee stated the closest access to electricity was 565 feet south of Lot 7 & to gain access to electrical service would require an easement over Endowment lands, through Lot 7. For the valuation of Lot 7, electrical service was discovered to exist. Currently, there is no electricity to Lot 6, so it is recognized the use of a generator is required (or combination of generator & solar panels). Lessee had previously indicated there is no septic system on this lot. They have used an outhouse but the SOW requires I assume a drainfield location exists.	
The 2018, 2021, 2022 & the 2023 valuations of this cottage site had shown an aggregate rating of 13 points although it could be argued the lot has the potential for 14 points when considering the road-to-building site that, through Lot 7, is more moderately sloping (higher rating). The slope from shoreline-to-building site is easily considered 4-5 points. Looking at the premiere feature of the expansive sandy beach area & shoreline usability, this is a higher rated site. The shallow depth (a more minor consideration) and the slopes from east down to west provide emphasis to the 13+ rating. None of this discussion addresses the fact the lot has no subdivision to the north & that there are only 2 lots in this southern part of Camp Cudge Landing. That is viewed both positively (buffer & seclusion) & negatively since the access road has cost share from only these two lots (Lots 6 & 7).			

Improvements: The Personal Property is defined as a residential/recreational single residential unit (together with any/all ancillary structures). The chart below is provided as a summary of these improvements. This identifies the class or quality of construction, year built, effective age, and other elements necessary for description and comparison. Please refer to the subject photographs as additional documentation of the improvements to be valued in this appraisal.

General Description					Foundation/Heating, Ventilating, A/C And Other Items				
Units	One	X	Ancillary Residential Units		N	Issues/Components		Remarks	
# of Stories	One story	X	1.5 Story		2 Story	Settlement	N		
Type	Det	X	Attached			Sump Pump	N		
Quality	Low Cost					Evidence of Infestation	N		
Design	Bungalow					Dampness	N		
Year Built	1925		County shows this was built in 1925 and the cabin contains 592 SF plus the EFP (enclosed front porch) of 77 SF.			EBB	N		
Condition	Old/Rustic					Elec. Wall Htrs	N		
Effective Age	50+					Forced Air Furnace	N		
Bathrooms	0					Cooling System	N		
Finished Area Above Grade	592					Wall Units	N		
Basement/Lower Level	0					Window Units	N		
Basement Finish	0					Central	N		
Attic	0			Fireplace/Wood Stove	1	Rock FP in living room.			
Utilities	None			Specialty Site Impvts.	X	Firepit, paths, parking area			
				Appliances		None			
Exterior Description					Interior Description				
Foundation	Post and pier foundation				Floors	Softwood flooring			
Exterior Walls	Mix of horizontal & vertical siding-painted.				Walls	T&G wood plank walls			
Roof Surface	Metal				Trim/Finish	Rustic wood			
Specialty Siding Elements	None				Ceiling Finish	no ceiling finish (exposed rafters)			
Gutters & Downspouts	None				Bath Floor	N/A			
Window Type	Single pane windows with storms/screens				Bath Wainscot	N/A			
Storm sash included	Yes		No	X	Deck/Porch/Patio(s)			107	SF
Screens	Yes	X	No		Garage (SF)			0	SF
Amenities	Lakeside deck on west side functions as entry porch (5' X 8'). This porch is deteriorated & appears unsafe.				Other Living Area			0	SF
					Outbuildings			0	SF
Fireplace/Wood Stove	Fireplace	Y	Wd Stove	N	FP insert	N	Dock (SF)	0	SF
Fencing	None	X				Boathouse (SF)		0	SF
Other Items	None	X				Seawall/Retaining Wall		0	LF
In addition to the main cabin, there is a building that was previously a guest cabin/storage building. The roof has collapsed & this is a detrimental condition to marketability. This is debris that has to be removed.					Main cabin appears to be a dry cabin as the former lessee stated there is no water system and no septic system. There is evidence of 2 plastic tanks above cabin & an above ground pump system to get water from lake to these tanks & then gravity flow to the cabin. None of that water system is truly functional without a sewage disposal system. No electricity, no plumbing, no water, etc. At best, this is a dry cabin.				
Appliances	Ref	0	Range/Oven	0	DW	0			
	Microwave	0	W/D	0	Gar. Disp.	0			
Room Count - Above Grade	Rooms	3	Bedrooms	1	Bathrooms	0.0			
Other Living Area	Old, fully deteriorated structure								

The cabin & the improvements noted here are classified as fully depreciated. There is little (marginal) to no value contribution to the cabin although I recognize a potential for interim use. The dilapidated or collapsed guest/storage building is viewed as a detrimental condition. There is no electrical service to the site. There is no water system and no septic system. The lessee has excluded the dock improvements so the only approved improvements are the road & driveway into the site. There is no evidence to suggest the road is anything more than providing legal & physical access to the cottage site. As such, I have concluded there is no value to the Personal Property.

HIGHEST AND BEST USE

The definition of Highest and Best Use was presented in the sales catalog. Please refer to that for the specific definition of this term.

Legally Permissible: The subject site is not zoned but is regulated by the Conditions, Covenants Restrictions (CC&Rs) as part of the official plat. Specific to the subject site, these CCRs have identified Use Restrictions such as “No Lot shall be occupied and used except for single-family residential purposes by the Owner and its family, or by a single-family tenant, which fits within the rustic character of the Idaho Panhandle National Forests. No more than one (1) Single-Family Dwelling shall be placed on the Property.” Mobile homes are not allowed but manufactured or modular homes on permanent foundation are allowed as long as there is compliance with minimum roof pitch and the improvement meets applicable building codes. There is a 40-foot setback from the high-water mark (lake front) as well as side yard and front yard setbacks of 15 feet and 25 feet, respectively. In addition, there are some regulations pertaining to colors of roofing & siding materials, & exclusion of perimeter fencing.

The key points of the CCRs are the regulation of the cottage site to a single-family residential use. This does not specifically address seasonality issues, the primary recreational considerations of the lake front qualities, availability of services including but not limited to schools, medical & hospital services, daily needs shopping, churches & other social services, etc. It simply states the cottage site will be used for single-family residential use and only one single family dwelling. Given the regulatory imposition of these CCRs as fundamental to the allowable land uses (per the recording of the subject subdivision); it is my opinion the only applicable use for this cottage site is a single residential dwelling unit (with ancillary living quarters if the lot size warrants it.

Physically Possible: The cottage site under study consists of the physically described property denoted in the Property Description section. There are no known characteristics that would eliminate the legally identified use of the property. There has been a weighted scale provided to this lot which measures it for such topographic characteristics as to slope under two measures; 1.) road-to-building site and 2.) shore-to-building site. Additionally, I have considered the quality & utility of the shoreline (beach) and the lake depth. However, I continue to find inconsistencies in the market as to whether shallow lake depth truly affects the market price of these waterfront parcels. In the past, it was argued that shallow depth required a longer, more costly dock, to gain adequate lake depth for boating. This followed that some impact to market value should be noted for the higher dock cost.

At the same time, the dock value is made a part of the Personal Property, so shallow lake depth is marginalized for the appraisal of the vacant cottage site.

Financially Feasible/Maximally Productive: The subject cottage site represents a single lot without benefit of future subdivision. This is intended to be a recreational lake frontage cabin site situated on the east side of Priest Lake. Although there is a potential for year-round living, the primary impetus for sellers and buyers has been the seasonal recreational utility afforded the waterfront sites along the shore of the lake. This is both a financially feasible use of the site, as vacant & unimproved and it is the maximal productivity of the site.

Timing of the Use: The subject site is immediately available for its highest and best use pursuant to the Scope of Work and the condition as a “vacant & unimproved” cottage site as a lake frontage tract.

Most Likely Use: The most likely use has been addressed under financial feasibility and maximal productivity.

Who is the Most Likely Buyer: The most likely buyer is a recreationist who desires the recreational attributes associated with a lake front site on Priest Lake and who has the financial means to invest in such a property? The largest population center having a direct effect on the Priest Lake market is Spokane, WA. In addition, there is Coeur d’Alene, Idaho although this city is situated along the shore of Coeur d’Alene Lake.

The Priest Lake market also attracts investor/users from Seattle, WA as well as throughout the Western U.S. Primarily, the seasonal recreational qualities would tend to attract those most able to utilize the property throughout the summer season and that is the most likely buyer. This statement cannot ignore the fact there are owners on Priest Lake that include at least one resident of Florida so geographically, the buyer profile is extensive but “most likely” would more logically apply to the Spokane population and radiate from there in a travel time/distance metric.

As Improved: The property is improved with a single residential dwelling unit as the primary use of the property. Based on a review of location, the main residential structure is in compliance with the CC&R’s that require a 40-foot setback from the lake. These same regulations eliminate all other uses except for a single residential dwelling unit and the defined ancillary structures. Key to this valuation is the expectations of the market relative to improvement size, qualities & function as they pertain to the quality of the lot.

The cabin & the improvements noted here are classified as fully depreciated. There is potentially some interim use value contribution to the main cabin but there is a detrimental condition in the collapsed guest cabin/storage building. There is no electrical service to the site. There is no water system and no septic system. The lessee has excluded the dock improvements so the only approved improvements are the road & driveway into the site. There is no evidence to suggest the road is anything more than providing legal & physical access to the cottage site. As such, I have concluded there is marginal value to the Personal Property.

THE APPRAISAL PROCESS

The appraisal process is an orderly procedure wherein the problem is defined, the work necessary to solve the problem is planned, and the data involved is acquired, classified, analyzed and interpreted into an estimate of value requested. There are three traditional approaches utilized by the appraisal professional which render a preliminary indication of value. They are generally referred to as the Cost Approach, the Income Approach and the Sales Comparison Approach. The discussion was contained in the sales catalog.

If the improvements are of relatively new construction, I will incorporate a cost approach within the appraisal. If, on the other hand, the improvements are old(er) and the market would clearly NOT rely on the cost approach, I will not present this valuation technique. County records show this dwelling was built in 1925. There has no remodeling & I recognize the old rustic appearance with no well water, no electrical services, no septic system and the deteriorated condition of the guest cabin/storage are detrimental to the marketability of the property. The existing improvements have reached the end of their useful life although they can be argued as having an interim use until new improvements can be developed. The road into the property is considered as a necessary element of the cottage site value which is legal & physical access and so this is not a site improvement. Nothing else is given value so the cost approach is not considered a credible valuation analysis.

This is not an income property, so the income approach is neither relevant nor applicable. Although it is recognized the cabin site & improvements could be rented out, the primary economic motivation that exists is for owner occupancy and/or use so the income approach has no direct relevance to establishing an opinion of market value.

Consistent with market behavior, the sales comparison approach is given primary emphasis. This recognizes the adage that a property is worth only what someone is willing to pay for it. The fundamental basis of that statement is clearly aligned with the foundation of the sales comparison approach. These are willing sellers and willing buyers, so the price recognizes the interaction of the parties that results in an indication of market price. When these sales (transactional data) are analyzed & compared to the subject, the adjusted indications form the basis for an opinion of value consistent with the weight given by market participants. When there is adequate market information available; both current and specific to the property being appraised, the credibility is proven. **The sales comparison approach is for the land only. I recognize the June 2023 sale of the subject leasehold estate so there is this one piece of improved sales data to consider.**

LAND VALUATION – SALES COMPARISON APPROACH

The site value was previously provided in the Fall of 2013 and in 2018, 2021, 2022 & 2023 VAFO appraisal cycle has incorporated both the lot value (vacant & unimproved) and a value of the fee simple estate for purposes of establishing the market value of the personal property (marginal contribution for dock, etc. set at \$25,000). The subject's land value has been developed via the sales comparison approach which is based on the premise that a buyer would pay no more for a specific property than the cost of obtaining a property with the same quality, utility, and perceived benefits of ownership. It is based on the principles of supply and demand, balance, substitution and externalities. The following steps describe the applied process of the Sales Comparison Approach.

- *The market in which the subject property competes is investigated; comparable sales, contracts for sale and current offerings are reviewed.*
- *The most pertinent data is further analyzed, and the quality of the transaction is determined.*
- *The most meaningful unit of value for the subject property is determined to be a price per square foot and a price per lot. The recreational issues involved are clearly supportive of the \$/SF as the primary unit of measure.*
- *Each comparable sale is analyzed and where appropriate, adjusted to equate with the subject property. It is my opinion there is no exclusivity in use, meaning the property can relate to both a recreational use as well as a residential use.*
- *The value indication of each comparable sale is analyzed, and the data reconciled for a final indication of value via a sales comparison technique.*

Property Rights Sold: The sales represent a fee simple conveyance where the transactions do not reflect unusual limitations to the private property rights associated with real estate ownership. The sales typically include utility easements where the easement is along a boundary line. There are no sales where an adjustment for property rights conveyed is necessary.

Financing Terms: The definition of market value requires the conclusion to represent a cash sale price or its' equivalent. There are many interpretations of what constitutes a cash sale, but emphasis should be on cash equivalency. In simple terms, where financing conditions may have affected the price paid, the sale is either excluded or an adjustment is made. This is not an issue for this appraisal as all sales reflect cash or equivalent financing terms.

Conditions of Sale: This relates to the motivational influences of each sale. Specific to discussion are sales that had been influenced by an atypical condition represented by the seller or the buyer such as a distressed sale where the seller was required to sell or the buyer was required to buy, and price was influenced outside of the definitional character of market. Such has been the case in bank sales disposing of property acquired through foreclosure, pending bankruptcy sales, buyers requiring a 1031 exchange where time required concessions, etc. The sales used are uninfluenced transactions relative to conditions of sale; seller and buyer not being under any undue influences to sell or purchase.

Market Conditions (Time of Sale): This measurement reflects the change in price levels over time. Key here is that *older sales are less reliable* as indicators of current market trends, for the very reason the market has not been consistent in how price levels have changed over time.

As taken from the 2024 sales catalog, I focused attention to LS-#1 which is 2106 Kalispell Bay Road. This hillside lot sold 9/16/2022 for \$1,250,000 but it included a “slip” dock which the broker stated was a dock with boat slip. The broker did not have an allocated value for the dock or the excavation done. These 2 – 50FF lots sold for a net price (my analysis) for \$1,225,000 or \$12,250/FF. This same property sold 11/27/2017, for \$725,000 and, at that time, there were \$31,000 in improvements allocated so the net land price was \$694,000. This is an overall appreciation of 76.51%. If the overall price were noted for comparison, this is \$725,000 that has appreciated to \$1,250,000 over this 62 +/- months. That is roughly 10.6% per year, monthly compounding. For the land only indications, this is \$694,000 appreciating to \$1,225,000 and that is a monthly appreciation of 12.6% simple annual increase. This is clear and convincing evidence of market appreciation over the time frame of November 2017 through September 2022.

The next matched pair was somewhat less direct. Lot 6, Sandy Shores Lane sold 12/8/2020 for \$569,000 (less \$12,000 for dock). This was a 0.30-acre tract with 100 FF of sandy beach frontage. Topography was mostly level. The dock contribution was deducted leaving \$557,000 to the site value or a unit price of \$5,570/FF. This lot had been on the market (on & off) since 2014 with a list price of \$665,000. This sale was then compared to the current LS-#3 which is Lot 3 Hess Point. This tract contained 0.59 acres with 132 FF & similar topography & shoreline qualities. This was a ULA lot transaction in the August 2022 auction. The lot sold for \$1,560,000 which is \$11,818/FF. It is recognized that there is a difference in frontage amount and Lot 6 being part of Huckleberry Bay which has sewer & water included and there are the other amenities of the subdivision. Adjusting down for those sewer & water and for size, this sale produced a 12/2020 adjusted value of \$4,766/FF. That is directly compared to \$11,818/FF from the N. Hess Point Sale & that represents a price appreciation of 53% annual appreciation.

For purposes of analysis, adjusting sales that occurred in 2021, I had adjusted upward for time using 3% per month on a straight-line basis and this is through all of 2022 as there is no evidence to suggest land values have become static since the last auction. The issue of scarcity has offset any issue associated with rising interest rates.

I have also looked at 1 improved property that sold and resold. This property is 213 S. Granite Bay Road. This was a 1/29/2016 sale for \$640,000 and it recently resold 9/18/2023 for \$1,250,000. Based specifically to the overall sale price, this is 8.728% per year (annual growth). The improvement is not felt to increase at this same level and analysis suggests a land appreciation, over this time frame, at 10%. The market appreciation during 2016 through 2019 was much less than what has been shown since 2020 through 2023 and it is my belief this helps support a long-term appreciation from 2016 to present but also the variability expressed over time where price growth has been more pronounced over the last couple of years.

Topography & Shoreline Characteristics (Lake Depth) fully define site usability. I have retained this topography adjustment on the basis of overall consistency in rating the IDL cottage sites from 2013 through this 2023 sales catalog. Although not an “absolute” measure, there is a method of quantifying physical features of the sales in comparison to the subject lots. I believe this remains a strong method of addressing overall site topography. The rating of 5-points for road-to-building site, the 5-points for shore-to-building site, the 4-points for shoreline qualities and the lake depth of 2-points are relevant although the shoreline qualities could absorb the lake depth and simply make that a 5-point rating which would mean a premium lot would be 15 points. I have not changed the 16-point total to be fully consistent with previous appraisals.

Shoreline Characteristics (Actual shoreline qualities & Lake Depth) are an integral part of topography, and these two issues were researched to determine if the market provided any quantifiable data to separate that analysis from the general discussion of site topography.

Based on experience, there does not appear to be a recreational market in this region, at least based on my research & analysis, that allows a quantifiable separation of site slope issues from the shoreline (beach) & lake depth qualities; especially lake depth issues which seem to be a personal choice consideration more than a value attribute.

Shoreline elements are comprised of both the beach as well as lake depth. Relative to shoreline and beach, the Priest Lake sub-market demonstrates fully usable sandy beach & shoreline that is termed the premium lot characteristics. The next quality rating is a mix of sandy/gravel and rocky/brushy shoreline. It assumes there is sufficient shoreline/beach that normal lake recreation is provided. The third classification is a shoreline/beach that is predominately rocky/brushy but still allows for development of a dock improvement and which provides a beach shelf or shoreline shelf where typically lakefront recreation can occur (firepit and a gathering area). The last category reflects a steeper topography with no truly usable beach or shoreline shelf. An example would be a site where stair access to the dock improvement comprises the lakefront recreation and all other parts of the shoreline are usable primarily for view protection and buffer. Shoreline/beach is measured on the basis of 4 points but could as easily be of equal weight as the topography shore-to-building site and road-to-building site which are both 5-point scales.

I have previously discussed lake depth as having a point scale of 1 or 2 with 1 reflecting shallow depth to such an extent that reaching boat depth requires a lengthy dock (more costly dock improvement). Additionally, very shallow lake bottom incorporates bottom vegetation (reeds, seaweed, etc.).

Topography: As stated in the sales catalog, the reader needs to be cognizant of the rating system that has been and is still being used. Item #1, Topography/Slope from “road-to-building site” is rated on the basis of a 5-point scale with extremely steep being worth 2-3 points and level being worth 5 points. To clarify, level (flat) to gentle slope is rated the same. For moderate slope, I have used a rating of 4.

A similar situation was incorporated for Item #2, Topography/Slope from “shore-to-building site” with steeper slopes being worth 2-3 points and level to gentle slope rated at 5 points. The topographic consideration of an elevated building site with a moderate slope (bank area), I have used a rating of 4 although there is market information that suggests there may not be a market perception of value impact for this topography variation.

It is my opinion the market does not react in a consistent manner when dealing with topography and shoreline qualities. Sometimes this is related to inventory (both scarcity and abundance) and sometimes these inconsistencies are related to the specific buyer(s) emotional reaction to a particular property. Common sense would dictate a level site is easier and less costly to develop when compared to a hillside lot, but the offsets are that the hillside lot provides the opportunity for a daylight lower level that is generally not available to the lot that is level and only slightly elevated above the lake. I have retained the same adjustment process for overall site topography (road-to-building, shore-to-building, shoreline/beach and lake depth) with premium lots at 15 to 16 points, Good quality lots at 13-14 points and steeper & of lesser overall quality at 12 points.

The original adjustment process did not have adequate transactional data to incorporate and over the years, the classification of topography has become more supported by data. This is both a qualitative as well as quantitative adjustment process.

Size Adjustment: The next issue of significance relates to a size adjustment. Theory holds that a smaller parcel should sell for a higher unit price (in this case, a higher front foot value) and conversely a larger tract should sell for a lower unit price. Discussions with several brokers who deal with Priest Lake and Lake Pend Oreille properties indicated an optimum size for a lake front parcel to be 100 feet of frontage yet there is no absolute standard for a lake front tract size.

Please refer to the sales catalog for the conclusion of a size adjustment. This is done on a very specific mathematical formula to remain consistent throughout the process but the final reconciliation has taken into account, the nuances of the size adjustment as well as the topography adjustment.

Located below is the tabulation of land sales presented in the 2024 sales catalog and this is followed by specific discussion of the previous years' VAFO results.

Land Sale #	Address/ Legal Description	Date of Sale	Sale Price	Impvt. Value	Land Value @ Sale	Unit Price (\$ / FF) @ Sale	Mkt Cond. Adj.	Feb. 15, 2024 Valuation	FF Size	SF Size	Topo R-BS + S-BS	Shore Rating	Lake Depth	Total Topo. Rating	\$/FF	DOM
1	441 Pinto Point Rd	11/7/2023	\$845,000	\$75,000	\$770,000	\$7,264	0	\$770,000	106.00	13,068	8	4	2	14	\$7,264	17
2	3 East Shore Rd	7/3/2023	\$360,000	\$0	\$360,000	N/A	0	\$360,000	None	45,738	N/A	N/A	N/A	N/A	N/A	42
3	324 N Hess Point Rd	8/26/2023	\$2,450,000	\$0	\$2,450,000	\$12,564	6.25%	\$2,603,125	195.00	27,443	10	4	2	16	\$13,349	37
4	390 Upper Bear Creek	8/26/2023	\$1,220,000	\$0	\$1,220,000	\$12,200	6.25%	\$1,296,250	100.00	20,038	7	3	2	12	\$12,963	37
5	822 Sherwood Beach Rd	8/26/2023	\$733,000	\$0	\$733,000	\$8,425	6.25%	\$778,813	87.00	12,197	6	3	2	11	\$8,952	37
6	375 Eight Mile Rd	8/26/2023	\$1,603,000	\$0	\$1,603,000	\$11,132	6.25%	\$1,703,188	144.00	47,480	10	4	2	16	\$11,828	37
7	2106 Kalispell Bay Road	9/16/2022	\$1,250,000	\$25,000	\$1,225,000	\$12,250	21.25%	\$1,485,313	100	20,473	8	4	2	14	\$14,853	75
8	30 Bartoo Island	7/14/2022	\$370,000	\$0	\$370,000	\$5,068	23.75%	\$457,875	73	94,090	8	4	2	14	\$6,272	40
9	NNA Upper Bear Creek Rd	8/13/2022	\$673,000	\$0	\$673,000	\$5,802	23.75%	\$832,838	116	28,750	7	3	2	12	\$7,180	67
10	NNA N. Hess Point Rd	8/13/2022	\$1,560,000	\$0	\$1,560,000	\$11,818	23.75%	\$1,930,500	132	25,700	10	4	1	15	\$14,625	46
11	NNA State Cabin Rd	8/13/2022	\$1,850,000	\$0	\$1,850,000	\$10,165	23.75%	\$2,289,375	182.0	46,609	10	4	1	15	\$12,579	54
13	NNA Beaver Creek Camp	3/1/2022	\$440,000	\$0	\$440,000	\$5,946	30.00%	\$572,000	74.00	15,377	9	4	1	14	\$7,730	564
14	47 Pinto Point Rd	8/21/2021	\$1,525,000	\$0	\$1,525,000	\$11,296	55.00%	\$2,363,750	135.00	43,124	10	4	1	15	\$17,509	39
15	6604 Eastshore Road	8/22/2021	\$810,000	\$0	\$810,000	\$5,294	55.00%	\$1,255,500	153.00	34,848	6	3	2	11	\$8,206	68
16	310 Powerline Road	8/23/2021	\$1,000,000	\$0	\$1,000,000	\$5,556	55.00%	\$1,550,000	180.00	56,628	6	3	2	11	\$8,611	83
17	48 E. Char Lane	8/24/2021	\$715,000	\$0	\$715,000	\$4,767	55.00%	\$1,108,250	150.00	39,640	8	3	2	13	\$7,388	72
18	503 Pinto Point Road	8/25/2021	\$750,000	\$0	\$750,000	\$7,075	55.00%	\$1,162,500	106.00	13,068	8	3	2	13	\$10,967	31
19	441 Pinto Point Road	8/26/2021	\$500,000	\$0	\$500,000	\$4,717	55.00%	\$775,000	106.00	13,068	8	3	2	13	\$7,311	39
20	1062 N. Steamboat Bay Rd	8/2/2021	\$4,000,000	\$35,000	\$3,965,000	\$11,138	55.00%	\$6,145,750	356.0	203,861	10	4	2	16	\$17,263	668
21	Lot 4 South Shores	1/5/2021	\$465,000	\$0	\$465,000	\$3,207	78.00%	\$827,700	145.0	25,700	6	3	2	11	\$5,708	328
24	Lot 6 Sandy Shores Ln.	12/8/2020	\$569,000	\$12,000	\$557,000	\$5,570	80.00%	\$1,002,600	100.0	13,024	10	4	1	15	\$10,026	309
25	78 Janet Lane	11/19/2020	\$1,200,000	\$0	\$1,200,000	\$6,936	83.00%	\$2,196,000	173.0	35,284	9	4	2	14	\$12,694	282
26	374 Upper Bear Creek	10/19/2020	\$625,000	\$0	\$625,000	\$4,921	85.00%	\$1,156,250	127.0	28,750	7	3	2	12	\$9,104	N/A

The summary of the 2023 VAFO/ULA Auction in August of 2023 is shown in the table below. There was only one sale that was to a non-lessee so there is added emphasis to that transaction. However, it is my opinion these other 3 sales bear some weight in the final analysis because there was competitive bidding and there was strength to the buyer motivations.

August 26, 2023 VAFO/ULA Auction											
Sale #	Address	Lot	Block	Subdivision	FF	Appraised Value	Value \$/FF	Winning Bid	Price \$/FF	Winning Bidder	Appraisal Rating
VAFO Results:											
VAFO 1	324 N. Hess Point Rd	2	1	Hess Point	195.00	\$1,814,000	\$9,303	\$2,450,000	\$12,564	Non-Lessee	15
VAFO 2	390 Upper Bear Creek Rd	9	1	Bear Creek	100.00	\$844,000	\$8,440	\$1,220,000	\$12,200	Lessee	12
VAFO 3	822 Sherwood Beach Rd	10	1	Kokanee Point	87.00	\$733,000	\$8,425	\$733,000	\$8,425	Lessee	11
VAFO 4	375 Eight Mile Road	38	1	Horton Creek	144.00	\$1,603,000	\$11,132	\$1,603,000	\$11,132	Lessee	16

The summary of the 2022 VAFO/ULA Auction in August of 2022 is shown in the table below. The two shaded rows are sales that do not truly represent market value behaviors. This is particularly true of VAFO 6 where the bidders were reported to have motivational influences atypical to common market forces. As will be noted, the 3 ULA auction sales were already incorporated into the land sales tabulation that will be emphasized for the vacant cottage site analysis to be part of this 2024 VAFO valuations.

August 2022 VAFO/ULA Auction											
Sale #	Address	Lot	Block	Subdivision	FF	Appraised Value	Value \$/FF	Winning Bid	Price \$/FF	Winning Bidder	Appraisal Rating
VAFO Results:											
VAFO 1	362 N. Cape Horn Road	2	1	Powerline	133.00	\$665,000	\$5,000	\$665,000	\$5,000	Lessee	12
VAFO 2	1174 Cape Horn Road	49	1	Woody's Point	146.00	\$794,000	\$5,438	\$794,000	\$5,438	Lessee	13-14
VAFO 3	410 N. Steamboat Bay Road	11	1	Soldier Creek	151.00	\$985,000	\$6,523	\$2,300,000	\$15,232	Lessee	15
VAFO 4	592 N. Steamboat Bay Road	3	1	Soldier Creek	158.00	\$1,031,000	\$6,525	\$1,600,000	\$10,127	Lessee	15
VAFO 5	64 Janet Lane	8	3	Powerline	154.00	\$1,013,000	\$6,578	\$2,400,000	\$15,584	Lessee	14
VAFO 6	179 Eight Mile Road	31	1	Horton Creek	172.00	\$1,115,000	\$6,483	\$9,800,000	\$56,977	Lessee	15
VAFO 7	122 Hess Point Road	13	1	Hess Point	300.00	\$2,160,000	\$7,200	\$2,900,000	\$9,667	Lessee	16
ULA (Unleased Land Auction) Results:											
ULA #1	NNA Upper Bear Creek Rd	12	1	Bear Creek	116.00	\$673,000	\$5,802	\$673,000	\$5,802	Non-Lessee	12
ULA #2	NNA Hess Point Road	3	1	Hess Point	132.00	\$901,000	\$6,826	\$1,560,000	\$11,818	Non-Lessee	15
ULA #3	NNA State Cabin Road	3	1	Two Mouth Creek	182.00	\$1,155,000	\$6,346	\$1,850,000	\$10,165	Non-Lessee	15

The summary of the 2021 auction data helps provide the basic evidence of leased sites being acquired by the existing lessee and the ULA or unleased site sales, which I believe should be emphasized; particularly when no improvements existed, or those improvements were of marginal consideration.

August 2021 VAFO/ULA Auction										
Address	Lot	Block	Subdivision	FF	Appraised Value	Value \$/FF	Winning Bid	Price \$/FF	Winning Bidder	Appraisal Rating
VAFO Results:										
354 N Cape Horn Rd	1	1	Powerline	136.00	\$420,000	\$3,088	\$575,000	\$4,228	Non-Lessee	11
1458 Cape Horn Rd	38	1	Woody's Point	150.00	\$645,000	\$4,300	\$645,000	\$4,300	Lessee	13+
76 W Horton Creek Rd	23	1	Horton Creek	150.40	\$499,000	\$3,318	\$855,000	\$5,685	Non-Lessee	11
38 S Horton Creek Rd	17	1	Horton Creek	161.00	\$523,000	\$3,248	\$610,000	\$3,789	Lessee	11-12
218 State Cabin Rd	11	1	Two Mouth Creek	142.00	\$753,000	\$5,303	\$753,000	\$5,303	Lessee	15
564 State Cabin Rd	2	1	Two Mouth Creek	173.00	\$783,000	\$4,526	\$1,570,000	\$9,075	Lessee	15
61 Pinto Point Rd	39	1	Pinto Point	146.00	\$690,720	\$4,731	\$690,720	\$4,731	Lessee	14+
572 Pinto Point Rd	18	1	Pinto Point	258.00	\$922,720	\$3,576	\$922,720	\$3,576	Lessee	14
42 N Eight Mile Rd	27	1	Horton Creek	156.10	\$765,000	\$4,901	\$765,000	\$4,901	Lessee	15
1563 W Pearl Shore	5	1	Outlet Bay	180.00	\$405,000	\$2,250	\$475,000	\$2,639	Lessee	13-14
ULA (Unleased Land Auction) Results:										
47 Pinto Point Rd	40	1	Pinto Point	135.00	\$649,720	\$4,813	\$1,525,000	\$11,296	ULA	14-15
6604 Eastshore Rd	1	1	Horton Creek	153.00	\$490,000	\$3,203	\$810,000	\$5,294	ULA	11
310 Powerline Rd	5	1	Woody's Point	180.00	\$536,000	\$2,978	\$1,000,000	\$5,556	ULA	11
48 E Char Ln	27	1	Woody's Point	150.00	\$519,000	\$3,460	\$715,000	\$4,767	ULA	12
503 Pinto Point Rd	21	1	Pinto Point	106.00	\$499,920	\$4,716	\$750,000	\$7,075	ULA	13
441 Pinto Point Rd	24	1	Pinto Point	106.00	\$499,920	\$4,716	\$500,000	\$4,717	ULA	13

An issue that has been resolved for purposes of presenting an opinion of market value is the extraordinary assumption that each lot will have adequate lot area to install an on-site system or have additional lands available for a community drainfield system (could be as small as a single home site drainfield off-site to as many as necessary to accomplish the “developability” of these cottage sites for private sewer service. The value of the off-site drainfield land is inherent in the lake (frontage) lot. There is no proportionate value to that off-site drainfield land. It is simply an absolute requirement that the individual cottage sites have either adequate on-site capacity for private sewer or they have an off-site location available for compliance with Panhandle Health District 1 regulations.

Located on the following pages are the grid analyses that pertains to the direct comparison of the land sales and how these sales reflect an indication of value for the subject site, after adjustments for waterfront size, topography and other physical dissimilarities. The Priest Lake market continues to evolve into what is perceived to be certain topographical characteristics where this lot has had previous appraisals at an overall rating of 13+ points. The classification of general topography is 8-points with shoreline/beach of 4 points and lake depth at 2 points and that is regarded as the most accurate reflection of topography qualities. However, there is no electrical service to the site & that focuses the classification down to the 13+ rating.

Categories	Subject Property	Land Sale #1	Adjustments	Land Sale #3	Adjustments	Land Sale #4	Adjustments	Land Sale #5	Adjustments	Land Sale #6	Adjustments
Address/Sale Price	1157 Camp Cudge Rd	441 Pinto Point Rd	\$770,000	324 N. Hess Point Rd	\$2,450,000	390 Upper Bear Creek	\$1,220,000	822 Sherwood Beach Rd	\$733,000	375 Eight Mile Rd	\$1,603,000
Property Rights Conveyed	Fee Simple	Fee Simple	\$0	Fee Simple	\$0	Fee Simple	\$0	Fee Simple	\$0	Fee Simple	\$0
Financing Terms	Cash Equivalent	Conventional	\$0	Cash	\$0	Cash	\$0	Cash	\$0	Cash	\$0
Conditions of Sale	Market	Market	\$0	VAFO	\$0	VAFO/ULA	\$0	VAFO/ULA	\$0	VAFO/ULA	\$0
Expenditures Made Immediate to Sale	None	None	\$0	None	\$0	None	\$0	None	\$0	None	\$0
Sale Date/Market Conditions	2/15/2024	11/7/2023	\$0	8/26/2023	\$153,125	8/26/2023	\$76,250	8/26/2023	\$45,813	8/26/2023	\$100,188
Adjusted Sale Price	N/A	No Adjustments	\$770,000		\$2,603,125		\$1,296,250		\$778,813		\$1,703,188
Adjusted Price (\$/FF)	N/A	No Adjustments	\$7,264		\$13,349		\$12,963		\$8,952		\$11,828
Adjustments:											
Location	Priest Lake	East Side Priest Lake	\$0	East Side Priest Lake	\$0	East Side Priest Lake	\$0	East Side Priest Lake	\$0	East Side Priest Lake	\$0
Size (SF)	36,590	13,068	In FF Size	27,443	In FF Size	20,038	In FF Size	12,197	In FF Size	47,480	In FF Size
Size (FF)	122.00	106.00	-\$354	195.00	\$2,886	100.00	-\$870	87.00	-\$956	144.00	\$1,145
Topography Classification (Slope)	Gentle-Mod. Steeper Slopes	Tiered with usable shoreline/beach	See Overall	Level to slight slope-sandy beach	See Overall	Varied Slopes/R-B Shore	See Overall	Varied slopes/gentle beach	See Overall	Level-Gentle & Sandy Beach	See Overall
Topography Rating	13	13-14	See Overall	16	See Overall	12	See Overall	11	See Overall	16	See Overall
Rating as % of Total - Comparison	0.8125	.8125-.875	See Below	1.0000	See Below	0.7500	See Below	0.6875	See Below	1.0000	See Below
Overall Topography Adjustment	Good Quality Lot; No Elec.	5.00%	\$363	-25.00%	-\$3,337	15.00%	\$1,944	25.00%	\$2,238	-25.00%	-\$2,957
Road Frontage	Camp Cudge Rd	Pinto Point Rd	\$0	N. Hess Point Rd	\$0	Upper Bear Creek	\$0	Sherwood Beach Rd	\$0	Eight Mile Rd	\$0
Utilities (sewer & water systems)	None but in Topo Rating	Elec. & Phone & Com. Drain.	In Adj. SP	Elec. & Phone	Land Sale Only	Elec. & Phone	\$0	Elec. & Phone	\$0	Elec. & Phone	\$0
Improvements and/or Common Areas	None	PP Com. Service Lot	In Adj. SP	N/A	\$0	Improvements	Land Sale Only	Improvements	Land Sale Only	Improvements	Land Sale Only
Zoning/Land Use Reg's	CC&Rs	CC&Rs	\$0	CC&Rs	\$0	CC&Rs	\$0	CC&Rs	\$0	CC&Rs	\$0
Net Adjustments			\$9		-\$451		\$1,075		\$1,282		-\$1,812
Indicated Value FF			\$7,273		\$12,898		\$14,037		\$10,234		\$10,016
Implied Subject Value			\$887,290		\$1,573,574		\$1,712,525		\$1,248,521		\$1,221,914
Low	\$887,290	This is a Pinto Point lot that includes access to the community drainfield & pro-rata share of community service lot. Topography of the site is consistent with sales to the north & south of this lot where the upper elevation is at-grade with road then gentle slope to bench, moderate slope to shoreline/beach area. All site improvements, including dock, have been deducted from sale price so what is shown is Land Only.			End of road location with level topography from road-to-building site & slight slope to shoreline/beach. Total rating of 16-points demonstrates premium lot quality. This was August VAFO having competitive bidding & non-lessee was successful bidder. Land was appraised at \$1,814,000 and upbid to \$2,450,000. Market price shown here was adjusted for market conditions.		Topography of this lot was rated at 12-points but the price paid is considered to be at a higher rating. This moderate to steeper bench area creates some different focuses on slope from road-to-shore. The lot was appraised for \$843,000 but sold under a competitive bid process at \$1,220,000 with lessee the successful bidder. The overall topography rating was 12-points but could be argued as high as 13-points due to site development.		Sale was rated at 11-points due to steeper slope from elevated building site to shoreline. There was a concrete retaining wall that had some structural issues; lessee said could be cured without major investment. This was appraised at \$733,000 & sold to lessee at that price (no competitive bidding). The small size, the shared driveway access & parking, the retaining wall issues & steeper slope to shoreline/beach were all factored into the price.		Lot is located near end of Eight Mile Road with level topography, adequate size for on-site parking and slightly elevated building site sloping gently to sandy/gravel shoreline. This is premium rated lot that was sold at appraised value to existing lessee; no competitive bidding. This is felt to be a strong indication of current market value for premium lot.
High	\$1,712,525										
Average	\$1,328,765										

Categories	Subject Property	Land Sale #7	Adjustments	Land Sale #9	Adjustments	Land Sale #10	Adjustments	Land Sale #11	Adjustments	Land Sale #13	Adjustments
Address/Sale Price	1157 Camp Cudge Rd	2106 Kalispell Bay Rd	\$1,225,000	NNA Upper Bear Creek Rd	\$673,000	NNA Hess Point Rd	\$1,560,000	NNA State Cabin Rd	\$1,850,000	NNA Beaver Creek Camp	\$440,000
Property Rights Conveyed	Fee Simple	Fee Simple	\$0	Fee Simple	\$0	Fee Simple	\$0	Fee Simple	\$0	Fee Simple	\$0
Financing Terms	Cash Equivalent	Cash	\$0	Conventional	\$0	Cash	\$0	Cash	\$0	Conventional	\$0
Conditions of Sale	Market	Market	\$0	VAFO/ULA	\$0	VAFO/ULA	\$0	VAFO/ULA	\$0	Market	\$0
Expenditures Made Immediate to Sale	None	None	\$0	None	\$0	None	\$0	None	\$0	None	\$0
Sale Date/Market Conditions	2/15/2024	9/16/2022	\$260,313	10/13/2022	\$159,838	9/22/2022	\$370,500	9/30/2022	\$439,375	3/1/2022	\$132,000
Adjusted Sale Price	N/A		\$1,485,313		\$832,838		\$1,930,500		\$2,289,375		\$572,000
Adjusted Price (\$/FF)	N/A		\$14,853		\$7,180		\$14,625		\$12,579		\$7,730
Adjustments:											
Location	Priest Lake	West Side Priest Lake	\$0	East Side Priest Lake	\$0	East Side Priest Lake	\$0	East Side Priest Lake	\$0	NW Side of Priest Lake	\$0
Size (SF)	36,590	20,473	In FF Size	28,750	In FF Size	25,700	In FF Size	46,609	In FF Size	15,377	In FF Size
Size (FF)	122.00	100.00	-\$997	116.00	-\$131	132.00	\$644	182.00	\$2,381	74.00	Offsets
Topography Classification (Slope)	Gentle-Mod. Steeper Slopes	Mod.-Gentle w/good beach	See Overall	Mod. Slope/R&B Shore	See Overall	Slight slopes-sandy/brushy shore	See Overall	Slight slope/sandy&gravel shore	See Overall	Ltd Bldg Site/Sandy Beach	See Overall
Topography Rating	13	14	See Overall	12	See Overall	15	See Overall	15	See Overall	13	See Overall
Rating as % of Total - Comparison	0.8125	0.8750	See Below	0.7500	See Below	0.9375	See Below	0.9375	See Below	0.8125	See Below
Overall Topography Adjustment	Good Quality Lot; No Elec.	-5.00%	-\$743	15.00%	\$1,077	-15.00%	-\$2,194	-15.00%	-\$1,887	0.00%	\$0
Road Frontage	Camp Cudge Rd	Kalispell Bay Rd	\$0	Upper Bear Creek Rd	\$0	Hess Point Rd	\$0	State Cabin Rd	\$0	Beaver Creek Camp	\$0
Utilities (sewer & water systems)	Elec. & Phone	Elec. & Phone	\$0	Elec. & Phone	\$0	Elec. & Phone	\$0	Elec. & Phone	\$0	On-site Septic/Com. Wtr	-\$351
Improvements and/or Common Areas	None	Dock & Site Impvts Excl.	Adjust SP	Cabin not included	\$0	None	\$0	Cabin not included	\$0	None	\$0
Zoning/Land Use Reg's	CC&Rs	CC&Rs	\$0	CC&Rs	\$0	CC&Rs	\$0	CC&Rs	\$0	REC	\$0
Net Adjustments			-\$1,739		\$946		-\$1,550		\$494		-\$351
Indicated Value FF			\$13,114		\$8,125		\$13,075		\$13,073		\$7,379
Implied Subject Value			\$1,599,887		\$991,273		\$1,595,120		\$1,594,947		\$900,205
Low	\$900,205	Lot is actually 2 - 50 FF lots comprising the 100 FF noted. This was previously improved with rustic cabin & newer dock. At time of sale, there was driveway down to cabin location near beach. This lot has a sandy beach & usable lake depth with rating of 14-points due to steeper driveway.		Aug. 2022 VAFO Auction (ULA Parcel). The appraisal had shown this to be a 12-point rating although this could be slightly higher based on the shore-to-building site topography. This was under contract on Aug. 15, 2022 so the market condition adjustment is from that date of October 1, 2022 per discussion.		Aug. 2022 VAFO Auction (ULA Parcel) & no current lessee. This was rated at 15-points due to the shallow lake depth so this could be viewed as conservative. The tract was appraised for \$901,000 and sold with significant upbidding. This is a premium lot for Priest Lake. The brush along the shore could be trimmed/removed to improve overall usability.		Aug. 2022 VAFO Auction (ULA Parcel) & no current lessee. This was rated at 15-points due to the Two Mouth Creek influence (shallow lake depth). Rating could be viewed as conservative. The tract was appraised for \$1,155,000 but sold with significant upbidding. This is a premium lot for Priest Lake. Tract went under contract 8/15/22 so mkt condition adjustment from that date.		Building envelope is 20' X 30' due to seasonal creeks & high groundwater. This is timbered parcel with sandy beach/shoreline. The location is not year-round as road is not plowed. The small building site is key to this unit price being low.	
High	\$1,599,887										
Average	\$1,336,286										

Categories	Subject Property	Land Sale #14	Adjustments	Land Sale #15	Adjustments	Land Sale #16	Adjustments	Land Sale #17	Adjustments	Land Sale #19	Adjustments
Address/Sale Price	1157 Camp Cudge Rd	47 Pinto Point Rd	\$1,525,000	6604 East Shore Road	\$810,000	310 Powerline Road	\$1,000,000	48 E. Char Lane	\$715,000	441 Pinto Point Rd	\$500,000
Property Rights Conveyed	Fee Simple	Fee Simple	\$0	Fee Simple	\$0	Fee Simple	\$0	Fee Simple	\$0	Fee Simple	\$0
Financing Terms	Cash Equivalent	Cash	\$0	Cash	\$0	Conventional	\$0	Cash	\$0	Cash	\$0
Conditions of Sale	Market	VAFO/ULA	\$0	VAFO/ULA	\$0	VAFO/ULA	\$0	VAFO/ULA	\$0	VFO/ULA	\$0
Expenditures Made Immediate to Sale	None	None	\$0	None	\$0	None	\$0	None	\$0	None	\$0
Sale Date/Market Conditions	2/15/2024	10/23/2021	\$838,750	9/22/2021	\$445,500	10/7/2021	\$550,000	9/26/2021	\$393,250	10/23/2021	\$275,000
Adjusted Sale Price	N/A		\$2,363,750		\$1,255,500		\$1,550,000		\$1,108,250		\$775,000
Adjusted Price (\$/FF)	N/A		\$17,509		\$8,206		\$8,611		\$7,383		\$7,311
Adjustments:											
Location	Priest Lake	East Side Priest Lake	\$0	East Side Priest Lake	\$0	East Side Priest Lake	\$0	East Side Priest Lake	\$0	East Side Priest Lake	\$0
Size (SF)	36,590	43,124	In FF Size	34,848	In FF Size	56,628	In FF Size	39,640	In FF Size	13,068	In FF Size
Size (FF)	122.00	135.00	\$1,002	153.00	\$1,062	180.00	\$1,595	150.11	\$911	106.00	-\$357
Topography Classification (Slope)	Gentle-Mod. Steeper Slopes	Slight slope/sandy-brushy shore	See Overall	Mod-Steep Slope/Rocky Brushy	See Overall	Mod-Steep/R&B Shore	See Overall	Mod. Slopes/Timbered	See Overall	Level-Mod./Sand-grvl beach	See Overall
Topography Rating	13	15	See Overall	12	See Overall	12	See Overall	13+	See Overall	13-14	See Overall
Rating as % of Total - Comparison	0.8125	0.9375	See Below	0.7500	See Below	0.7500	See Below	0.8125	See Below	.8125-.875	See Below
Overall Topography Adjustment	Good Quality Lot; No Elec.	-15.00%	-\$2,626	15.00%	\$1,231	15.00%	\$1,292	5.00%	\$369	5.00%	\$366
Road Frontage	Camp Cudge Rd	Pinto Point Road	\$0	N. Horton Creek Rd	\$0	Cape Horn to Powerline Rd	\$0	Cape Horn to Char Ln	\$0	Pinto Pt. Road	\$0
Utilities (sewer & water systems)	Elec. & Phone	Com. Drainfield	\$0	Well or Lk & Septic Rq'd	0	Elec. & Phone in Price	\$0	On-site septic/well req'd	\$0	Lk Wtr/Com. Drainfield	\$0
Improvements and/or Common Areas	None	PP Com. Service Lot	-\$13	None	0	No Impvts	\$0	None	Adjust. SP	PP Com Service Lot	-\$16
Zoning/Land Use Reg's	CC&Rs	CC&Rs	\$0	CC&Rs	\$0	CC&Rs	\$0	CC&Rs	\$0	CC&Rs	\$0
Net Adjustments			-\$1,638		\$2,293		\$2,886		\$1,280		-\$7
Indicated Value FF			\$15,871		\$10,499		\$11,498		\$8,663		\$7,304
Implied Subject Value			\$1,936,311		\$1,280,830		\$1,402,702		\$1,056,900		\$891,100
Low	\$891,100	Aug. 2021 VAFO Auction with lot under contract 8/24/21 & mkt cond. Adjustment from this date. The lot is mostly level, some tree & brush cover & very usable sandy beach/shoreline. This lot was appraised for \$649,720 (\$1,760 for PP Com. Service Lot) with strong upbidding occurring. The adjacent property was sold to existing lessee for appraised value so bracket between this sale & that VAFO sale was emphasized,		Aug. 2021 VAFO Auction. This lot did not have an existing lessee. Topography was mod.-steeper slopes from East Shore Road to building site area. Access to the lot is from the north. This does not have a parking area shown as prior lessee had a walk in access to the cabin. There is an elevated building site with a rocky/brushy shoreline & small sandy beach at dock. No specific value given the dock which might impact price slightly.		Aug. 2021 VAFO Auction. This lot did not have an existing lessee. Topography was mod.-steeper slopes from Powerline Rd to building site area. The lot has rock outcroppings and overall topo rating was 11-12 points. Shoreline is mostly rocky & brushy. Under contract 8/24/21 which is date used to adjust. mkt conditions. There was rock pier at shoreline.		Aug. 2021 VAFO Auction. Gentle to Moderate slopes (some steeper). Timbered tract with road/driveway access to lake (historic ramp). Cobble & rocky shoreline & small sandy beach area. Slopes will allow a daylight basement reasonably close to shoreline. The appraisal for the auction was \$519,000 so significant upbid occurred.		Tract is at-grade & sloping from Pinto Point Road to the bench which is a moderately sloping hillside to the shoreline/beach area. This lot has a mix of sandy/gravel beach and brushy shoreline. The overall slope rating was 13 but the shoreline could be considered slightly better than previous appraisal. This lot at \$750,000 is directly comparable to the sale of 441 Pinto Point that sold for \$500,000.	
High	\$1,936,311										
Average	\$1,313,568										

Reconciliation of Land Valuation:

The 15 sales that have been used include 2023 sales, 2022 sales and some from the 2021 ULA sales. My analysis of the market & my final opinion have also incorporated the improved sales presented in the 2024 Sales Catalog. I have no market evidence that directly supports a price trend extending through the late Fall of 2023 to the date of value of February 15, 2024. I do believe there is some probability that market prices will continue but that is more conjecture and not truly fact-based analysis. Even with the volume of improved property sales and broker comments about continued strong demand, there is the risk that continued appreciation may not continue through this new year.

The table below is a reflection of the 15 sales incorporated into this analysis. There are some sales that I feel may not be true indicators of “typical” market given underlying considerations (e.g., neighbors who bid to remove a lessee, wanted to assemble, etc.).

All 15 Indications	Dollar Per FF	Value Indication
Mean (Average)	\$10,871	\$1,326,207
Median	\$10,499	\$1,280,830
Minimum	\$7,273	\$887,290
Maximum	\$15,871	\$1,936,311

The emphasis in this appraisal has factored the overall topography elements including, but not limited to, what is perceived to be the primary valuation; shoreline qualities & the use/location of the building site as proximate to the shoreline (slope issues). For this appraisal, I relied on market extraction for overall slope & shoreline qualities as discussed in the sales catalog. As I stated previously, the rating of 13+ points for this lot is argued as entirely reasonable given the moderate to gentle slope from shore-to-building site and then the east slope down to the building site which formed the conclusion of 8 points, to which is added the 4 points for shoreline qualities and 2 points for lake depth. The lack of electrical service is factored into the overall equation so 13+ is noted for this site.

I also reviewed the sales without including Sales #4, #7, & #14 based on either the inconsistencies noted in how these directly compare to the subject and/or based on transactional data at the time of sale for these lots that has questions their reliability as market value indicators.

Eliminated Sales #4, #7, & #14	Dollar Per FF	Value Indication
Mean	\$10,003	\$1,220,365
Median	\$10,125	\$1,235,217

Giving less weight (25%) to the mean of all 15 sales and greater weight (75%) that eliminates these three sales that are deemed less credible as market value indicators, resulted in a unit value of \$10,220/FF.

I feel it necessary to emphasize the 2023 VAFO sale of Lot 38 which sold to the lessee for appraised value. That is reflective of August 2023 but the date of value was January 2023 so some market condition adjustment is felt warranted. That property sold for \$1,603,000 and updated for time of sale, the current indication is \$1,703,188 or \$11,828/FF.

I would also like to acknowledge a premium quality lot that is identified as Land Sale #3 at 324 N. Hess Point Road (also known as 310 N. Hess Point). This was appraised at \$1,814,000 or \$9,303/FF but sold under strong competitive bidding, to a non-lessee for \$2,450,000 or \$12,564/FF. The key is the demand & resulting increase in lot price paid.

There is an extraordinary assumption associated with this analysis. I have previously appraised Lot 7 and this lot had power extended from the south. The cabin had a 100-amp service panel and there was lake water extraction and on-site septic to that property. It is assumed power could be extended from Lot 7 to the subject Lot 6. At the same time, a propane gas generator could be utilized for power and this would be reasonably acceptable for seasonal use. I have also considered the extension south from Lot 4, Camp Cudge Landing. I was unable to verify the cost to extend but there is a legal road & utility easement providing electrical power from that point. The cost to extend power was not determined but Northern Lights, Inc., which utility services the east side of Priest Lake, indicated the cost could be \$60,000 to \$75,000 but depends on clearing, topography and distance. What this provides is that power is available but at a cost. There is the potential to extend power from the south (Lot 7, Camp Cudge) and there is the use of a generator and/or solar panels, etc. All of this was considered in the topography rating & the valuation noted herein.

My conclusion is a site value based on the unit price of \$10,220/FF and that is applied to the subject frontage as indicated herein and that results in a value for the vacant & unimproved cottage site as shown below:

One Million Two Hundred Sixty-Seven Thousand Dollars

\$1,247,000

IDL Approved Improvements (Personal Property): For the fee simple valuation of this property (land & all improvements owned), the critical overview is whether the existing improvements add to the value of this site. The property is a 0.84-acre tract that is gently to moderately sloping with the current building site reflecting a reasonable location for a daylight basement construction. The existing cabin is too small for the quality of the lot. The damaged shed is a detriment given the current condition with no roof and walls caving in. The dock has been excluded by the current lessee so there is nothing else that adds to personal property. The previously noted lake water extraction system had a pump & the generator/piping but this is of such rudimentary engineering that I do not believe a new cabin would utilize any of the existing water system (if such even exists). The lessee has not addressed this system in terms of Seller Disclosure. As a result, I have not given this any contributory value. There is no septic system and the outhouse will not add to the overall value of the property. There is an assumption as to the availability of power (electricity) to the site and/or a means of extending power or using an on-site generator, solar array, etc. Road access to the site is integral to the cottage site where this provides legal & physical access to the cottage site. The driveway is located on Lot 7 and that is not an improvement to this tract.

Previously, the subject had a dock of 534 sq.ft. and that had a contributory value of \$26,700. The lessee has excluded that from the Bill of Sale. The 2023 valuation had indicated \$6,300 for the shared driveway, potential for electrical, & the building site clearing. It is my opinion there is little to no value allocated to the existing improvements. Which then focuses on the recent sale of the leasehold estate. This is shown as Sale #15 as presented in the sales catalog.

The subject leasehold was an MLS sale that stated, "**SOLD AT TIME OF LISTING**" The leasehold was priced at \$50,000. The sale price is reported to be \$50,000 with cash terms. This had 0 days on market. The sale included all site & structural improvements, including the dock and any appliances. For this appraisal, the dock improvement and the appliances are excluded as part of the Bill of Sale exclusions. If the dock improvement of \$26,700 were a reasonable indication of contribution value, then the remainder of the leasehold represents \$23,300. Deducting all of the appliances & other personal property, it is my belief that this could reflect a contribution value of \$20,000.

The purchaser of the leasehold is the existing owner of both 1159 Camp Cudge Road (Lot 7) and the larger property to the south of Lot 7. There are motivational elements to why this lessee purchased the leasehold immediately and it suggests there is no true Personal Property value outside the motivations of this one buyer. The removal of the dilapidated guest cabin/storage shed is a negative feature that is offset by any salvage value attributed to the existing cabin. It is my conclusion there is marginal Personal Property value that exists.

Sales Reconciliation: I do not believe the current market would accept or consider an allocation for the existing water system. Either a well would be drilled or a new lake extraction system would be expected with filtration, etc. The cabin is too rustic and too small for the quality of this lot and I have classified this as a "tear-down" although there is some expectation that this could have an interim value; such as use during construction of a new cabin or to allow seasonal use until a permanent year-round structure could be built.

The road into the lot is part of the cottage site's value. There is no electrical power to the lot and the cost to extend is substantial. The ability to use a mixture of solar and propane gas generator would allow seasonal use without the cost to extend power. The Bill of Sale excludes the appliances (marginal) and the dock which has a higher value contribution. By that exclusion, there is very little remaining that is allocated to the Personal Property when looking at the June 13, 2023, sale of the leasehold. There are motivational aspects that support my conclusion there is marginal market value to the Personal Property. I did not adjust (negatively) for the damaged shed nor did I deduct for the demolition of the main cabin.

Based on the sale of this leasehold in June of 2023 for \$50,000 and deducting for the Bill of Sale exclusions, it is my opinion a maximum allocation of \$20,000 is attributed to the Personal Property.

FINAL RECONCILIATION

In this appraisal, I have not incorporated the cost approach based on the 1925 construction and the overall layout of this rustic cabin. The cost approach is simply not relevant.

As discussed, lake front property on Priest Lake is in reasonably strong demand. There are sales of steeper sloping lots with older cabins where those improvements continue to add or contribute to overall value. There are premium lots where older cabins have been purchased and then demolished. It is imperative to understand the Priest Lake market has some inconsistencies in how improvement contribution is viewed. Lake front property on Priest Lake is in reasonably strong demand. There are sales of steeper sloping lots with older cabins where those improvements continue to add or contribute to overall value. There are premium lots where older cabins have been purchased and then demolished. The subject is an example of a cabin having no economic contribution.

The sales comparison approach has strength on the basis of the concept of substitution (acquiring a like-kind property having similar size, age/condition, qualities, site development, etc.) *In this situation, the sales comparison approach has not been employed in the traditional sense of the approach because the existing improvements should be demolished & new construction initiated to capture the quality of this site.* There are no site improvements other than the shared driveway. The Bill of Sale exclusions eliminated consideration of the dock. There is no electrical service and the road access is part of the cottage site although the shared driveway could be argued as partly attributed to the subject lot. The cabin & outbuilding contribute limited value to the site and could be argued as being a detriment. What I have observed when cabins have been sold that reflect the same issues as the subject, the buyer simply assumes the responsibility to demolish. I do recognize the main cabin could have an interim use value & that has been recognized in this appraisal.

This opinion reflects my opinion of the market value of the subject property under a fee simple valuation. Further, there is the value opinion for the cottage site as though a vacant & unimproved site but there is limited or marginal leasehold improvement value (personal property value), noted or supportable. The following is the marginal allocation of \$20,000 for the Personal Property together with the primary value component which is the market value of the cottage site.

Sales Comparison Approach	\$1,267,000
----------------------------------	--------------------

As the sales comparison approach – Land Only is the only valuation approach utilized, there is no need for reconciliation. The indication presented for the cottage site as vacant & unimproved plus the marginal allocation to the existing cabin for an interim use is the final valuation.

Based upon my investigations, studies and analyses, it is my opinion the encumbered *fee simple* market value of the subject property, reflecting the Extraordinary Assumption relative to IDL Approved Improvements & excluding any boat lifts or PWC lifts and reflecting the Bill of Sale exclusions, as of February 15, 2024, is:

One Million Two Hundred Sixty-Seven Thousand Dollars
\$1,267,000

Further, it is my opinion the market value of the subject property defined herein as the “vacant & unimproved” cottage site (***Land Only***), reflecting the hypothetical condition of that definition of “Vacant & Unimproved” and the Extraordinary Assumption regarding date of inspection vs. the effective date of value denoted herein as February 15, 2024, is:

One Million Two Hundred Sixty-Seven Thousand Dollars
\$1,247,000

Finally, it is my opinion there is no market value of the Leasehold Personal Property (IDL Approved Improvements Only) where no electrical service has been extended, there is no water system nor is there a septic system & only a rudimentary (shared) driveway/parking improvement for the subject lot.

Twenty Thousand Dollars
\$20,000

VALUE ESTIMATE AND CERTIFICATION

I certify that, to the best of my knowledge and belief:

- The statements of fact contained in this report are true and correct.
- The reported analyses, opinions, and conclusions are limited only by the reported assumptions and limiting conditions and are my personal, impartial, and unbiased professional analyses, opinions, and conclusions.
- I have no (or the specified) present or prospective interest in the property that is the subject of this report and no (or the specified) personal interest with respect to the parties involved.
- I have performed an appraisal of this property for the 2013 original contract and then again in 2018, 2021, 2022 & 2023. I appraised this property in 2022 and 2023 as a VAFO appraisal that included Personal Property. For the individual appraisals to be conducted for this latest cycle, I will cite specific acknowledgement whether that property has been appraised in the last three years.
- I have no bias with respect to the property that is the subject of this report or to the parties involved with this assignment.
- My engagement in this assignment was not contingent upon developing or reporting predetermined results.
- My compensation for completing this assignment is not contingent upon the development or reporting of a predetermined value or direction in value that favors the cause of the client, the amount of the value opinion, the attainment of a stipulated result, or the occurrence of a subsequent event directly related to the intended use of this appraisal.
- My analyses, opinions, and conclusions were developed, and this report has been prepared, in conformity with the Uniform Standards of Professional Appraisal Practice.
- I have made a personal, detailed inspection of the sales & listings consulted for this sales catalog.
- No one provided significant real property appraisal assistance to the person signing this certification. (If there are exceptions, the name of each individual providing significant real property appraisal assistance must be stated.)
- The report contains necessary discussion concerning a reasonable exposure period for the subject property within the estimated value shown.
- This report is in compliance with applicable regulations governing appraisal services and appraisal reporting requirements for the State of Idaho.
- The reported analyses, opinions, and conclusions were developed, and this report has been prepared, in conformity with the requirements of the Code of Professional Ethics & Standards of Professional Appraisal Practice of the Appraisal Institute, which include the Uniform Standards of Professional Appraisal Practice.
- As of the date of this report, I, Steven A. Hall, MAI, CCIM, have completed the continuing education program of the Appraisal Institute.
- The use of this report is subject to the requirements of the Appraisal Institute relating to review by its duly authorized representatives.

Based upon my investigations, studies and analyses, it is my opinion the encumbered *fee simple* market value of the subject property, reflecting the Extraordinary Assumption relative to IDL Approved Improvements & excluding any boat lifts or PWC lifts and excluding the dock, as of February 15, 2024, is:

One Million Two Hundred Sixty-Seven Thousand Dollars

\$1,267,000

Further, it is my opinion the market value of the subject property defined herein as the “vacant & unimproved” cottage site (*Land Only*), reflecting the hypothetical condition of that definition of “Vacant & Unimproved” and the Extraordinary Assumption regarding date of inspection vs. the effective date of value denoted herein as February 15, 2024, is:

One Million Two Hundred Sixty-Seven Thousand Dollars

\$1,247,000

Finally, it is my opinion the market value of the subject property defined herein as the Leasehold Personal Property (IDL Approved Improvements Only), reflecting the hypothetical condition of the cottage site as “Vacant & Unimproved” and the Extraordinary Assumption relative to IDL Approved Improvements, excluding any boat lifts or PWC lifts, dock improvements & all appliances, as of February 15, 2024, is:

Twenty Thousand Dollars

\$20,000



Steven A. Hall, MAI, CCIM

Idaho CGA-257

Expires 8/11/2024